

SPECIFICATIONS FOR 22-5730

Perform the semiannual and annual testing of the fire alarm systems, including but not limited to, testing of 110V Stand Alone Smoke Detectors, initiating devices, notification appliances, bed shaker outlets, relay & monitoring modules, testing of the power backup system and sensitivity testing following the contract guidelines and the National Fire Protection Association (NFPA) codes, Underwriters Laboratory (UL), Wisconsin Department of Commerce (DOC), Madison Fire Department (MFD) and National Electrical Code (NEC). Sensitivity testing to be conducted yearly unless code requires a more frequent schedule. 110v Stand Alone Smoke Detectors shall be tested semiannually unless code requires a more frequent schedule.

When a fire protection system is impaired (i.e. taken out of service), EH&S, UWPD dispatch, MFD, and UW Housing shall be notified immediately and, where required, the building shall either be evacuated or an approved fire watch shall be provided for all occupants left unprotected by the impairment until the fire protection system has been returned to normal service. Impairment form: <https://ehs.wisc.edu/fire-life-safety/fire-protection-uw-impairment-form/> The impairment coordinator for UW-Madison is Jeff Schiller (608)-265- 9080 from Environment Health & Safety. Please contact him prior to beginning work.

Contractor must provide all supplies and equipment required to do the testing. Testing shall be done on a continuous basis and based on Housing's schedule. At completion of the annual testing the contractor is to supply Housing with a list of all devices, their locations, and date last tested. Contractor must test every device, if access is an issue then they must contact a supervisor to gain access. Failure to test a device will result in a penalty per section 5.8.

Fire alarm systems shall be inspected, tested, and maintained in accordance with IFC 907.8.5. and NFPA 72, 2019 edition, Section 14. Contractor must submit annual inspection, testing, and maintenance reports filed electronically with the City of Madison in accordance with MGO 34.03(2) at: <https://elam.cityofmadison.com/CitizenAccess/Default.aspx>

The contractor shall inform Housing staff in writing of any new National Fire Protection Agencies (NFPA), Underwriters Laboratory (UL), Wisconsin Department of Commerce (DOC), Madison Fire Department (MFD), and National Electrical Code (NEC) codes or code changes through the life of this contract. If the applicable codes are updated during the contract period, the frequencies and testing are to be adjusted to reflect the changes.

New systems and devices may be installed at some locations during the life of the contract. Contractor should promptly notify Purchasing and Housing of devices count changes.

Follow all manufacturer testing guidelines that are required in addition to completing code requirements. Provide a list of any code deficiencies. Provide a report on any recommendations of service, including panel firmware versions and any updates that are available. Contractor to provide and ensure each panel has a current USB drive containing the programming of the building. A copy of these USB drives shall be submitted with the annual testing report. Contractor must set up their own reports and not rely on previous vendors work. Contractor to update all fire alarm building documents and floor plan data with device locations changes. PDF or paper documents and blueprints should be at the panel locations, if documents are missing, the contractor is responsible to re-create this information. The contractor is responsible to update these documents at the panel locations and include the updated PDF copy of the documents and blueprints with the annual report.

The contractor shall provide, within ten (10) days or as mutually agreed upon by contractor and contract administrator, two (2) hard and five (5) USB electronic copies of the testing, including but not limited to: Fire detection/suppression system generated report of field device test responses records; a listing of all equipment problems and two (2) written letters on company letterhead certifying that all required testing has been completed and meets the current codes. Reports are to be delivered to the proper Housing staff for approval. No invoices will be paid until testing reports are submitted to and approved by Housing.

Contractor must report to the department contact all life safety issues and potentially detrimental site conditions that could compromise the performance of the system, prior to leaving the site.

All systems must be returned to normal and in operating condition before leaving the site.

The contractor is to schedule testing with the Lakeshore Supervisor (608-262-0756) for the Lakeshore Area and Southeast Supervisor (608-262-6985) for the Southeast Area. If neither can be reached, then contact the Director of Maintenance (608-262-6702). Schedule with the University Apartments Director of Facilities (608-262-1018) for University Apartments. The Contractor will be required to attend a pre-test meeting prior to performing any testing, a meeting after testing is complete to discuss the testing and any deficiencies found, and any other meetings that Housing determines to be necessary.

Testing must be performed Monday through Friday, between the hours of 7:30 a.m. and 4:30 p.m., unless otherwise approved by contract administrator. Testing will occur during the months of April and October for University Apartments and January, June, July, and August for the Residence Halls. Testing locations and times must be agreed upon by UW Housing and contractor prior to test days. Failure to meet these testing conditions will disqualify your bid.

Contractor must have a minimum of five (5) years' experience testing fire alarm systems.

Contractor must be able to provide proof of certification by NICET (National Institute for Certification of Engineering Technicians) if requested. A minimum of one certified technician required on site during testing.

Contractor's staff must be properly trained for the systems they will be testing, qualified and competent to perform the services required by this contract using industry accepted standards, with a minimum 1-year experience on each system. Contractor must provide an insurance certificate upon notification of award.

SOUTHEAST AREA:

BUILDING	ADDRESS	BUILDING	ADDRESS
WITTE HALL	615 W. Johnson	GORDON COMMONS	717 W. Johnson Street
OGG HALL	835 W. Dayton Street	SMITH HALL	35 N. Park Street
SELLERY HALL	821 W. Johnson Street	MERIT HALL	917,919,921 W. Dayton St
CHADBOURNE HALL	420 N. Park Street	DAVIS HALL	917 W. Johnson Street
BARNARD HALL	970 University Avenue	ZOE BAYLISS HOUSE	915 W. Johnson Street

LAKESHORE AREA:

BUILDING	ADDRESS	BUILDING	ADDRESS
WATERS HALL	1200 Observatory Drive	CONOVER HOUSE	1650 Kronshage Drive
CARSON GULLEY	1515 Tripp Circle	SWENSON HOUSE	645 Elm Drive
TRIPP HALL	1510 Tripp Circle	JONES HOUSE	655 Elm Drive
ADAMS HALL	1520 Tripp Circle	CHAMBERLIN HOUSE	665 Elm Drive
SLICHTER HALL	625 Babcock Drive	HOLT COMMONS	1650 Kronshage Drive
TURNER HOUSE	1620 Kronshage Drive	COLE HALL	625 Elm Drive
GILMAN HOUSE	1610 Kronshage Drive	SULLIVAN HALL	635 Elm Drive
JORNS HALL	650 Babcock Drive	BRADLEY HALL	650 Elm Drive
HUMPHREY HALL	640 Babcock Drive	PHILLIPS HALL	1950 Willow Drive
MACK HOUSE	1630 Kronshage Drive	DEJOPE HALL	640 Elm Drive
SHOWERMAN HOUSE	1650 Kronshage Drive	LEOPOLD HALL	1635 Kronshage Drive
KRONSHAGE HALL	1650 Kronshage Drive		

UNIVERSTIY APARTMENTS:

BUILDING	BUILDING NUMBER	ADDRESS
UNIVERSITY HOUSES	1, 2, 3, 5, 6, 7, 9, 10, 11, 13, 14, 15, 17, 18, 19, 21, 22, 23, 25, 26, 27, 29, 30, 31, 33, 34, 35, 37, 38, 41	
UNIVERSITY HOUSES CHILDCARE CENTER	39	
HARVEY STREET APTS	1, 2, 3, 4, 5, 6 AND 7	2924 HARVEY ST.
EAGLE HEIGHTS COMMUNITY & CHILDCARE CENTER		611 EAGLE HEIGHTS DR.

EAGLE HEIGHTS APTS	101, 102, 103, 104, 105, 106, 107, 108, 109, 201, 202, 203, 204, 205, 206, 207, 208, 209, 301, 302, 303, 304, 305, 306, 307, 308, 309, 401, 402, 403, 404, 405, 406, 407, 408, 501, 502, 503, 504, 505, 506, 507, 508, 509, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 701-703, 704-705, 706, 707, 708, 801-808, 809-819, 901-911, 912-914, 915-917, 918-925, 926-928, 929-931, 932-934, 935-946	
WAREHOUSE COMPLEX		2902 HAIGHT ROAD
SERVICE BUILDING		2902 HAIGHT ROAD
EH 200 STORAGE BUILDING		200 EAGLE HEIGHTS DR.

DEVICE QUANTITIES: The following is a list of devices located in each building. The listed quantities of devices are believed to be accurate and are to be used for the purpose of bidding. Prices may be adjusted consistent with contract prices based on actual devices if there are any discrepancies after contract is awarded.

Building	Area	MFG	Panel	NAC	Smoke	Duct	Heat	Pulls	Strobe	Horn	Horn Strobe	Battery Count	Stairwell Pressure	Elevator Recall	DAS / BDA	Relay Modules	Monitor Module	110 VAC SmokeDetector
Adams	RH	Simplex	4100	4	151	UNK	32	40	57	220	90	10	n/a	n/a	n/a	UNK	UNK	241
Barnard	RH	Notifier	AFP-400	3	91	UNK	2	26	25	131	71	8	n/a	n/a	n/a	UNK	UNK	134
Bradley	RH	Siemens	MXLV	2	96	UNK	8	17	27	124	83	6	n/a	n/a	n/a	UNK	UNK	145
Carson Gulley	RH	Simplex	4100ES	2	44	UNK	19	1	3	n/a	64	6	n/a	n/a	n/a	UNK	UNK	n/a
Chadbourne	RH	Siemens	MXOV	11	569	39	49	76	28	314	181	24	n/a	2	n/a	UNK	UNK	n/a
Chamberlain	RH	EST	EST-3	1	33	1	8	8	3	40	12	4	n/a	n/a	n/a	UNK	UNK	40
Cole	RH	Simplex	4100U	8	218	UNK	23	1	17	132	72	10	n/a	n/a	n/a	UNK	UNK	n/a
Conover	RH	EST	EST-3	1	25	1	10	10	7	47	10	4	n/a	n/a	n/a	UNK	UNK	42
Susan Davis	RH	Notifier	5000	n/a	16	UNK	10	8	n/a	n/a	11	2	n/a	n/a	n/a	UNK	UNK	31
Dejope	RH	Notifier	NFS3030	8	376	37	52	1	33	383	300	18	n/a	2	n/a	UNK	UNK	383
Waters	RH	Simplex	4100	10	393	27	90	1	69	251	83	14	n/a	1	n/a	UNK	UNK	264
Gilman	RH	EST	EST-3	1	35	UNK	8	8	8	39	11	4	n/a	n/a	n/a	UNK	UNK	40
Gordon Commons	RH	Simplex	4100ES	8	102	11	50	22	17	11	201	18	n/a	n/a	n/a	UNK	UNK	n/a
Holt Commons	RH	Notifier	NFS640	n/a	7	2	5	3	9	n/a	26	2	n/a	n/a	n/a	UNK	UNK	n/a
Humphrey	RH	Edwards	EST3X	n/a	n/a	1	10	1	2	38	32	2	n/a	n/a	n/a	UNK	UNK	n/a
Jones	RH	EST	EST3	1	34	1	7	8	3	40	12	2	n/a	n/a	n/a	UNK	UNK	40
Jorns	RH	Edwards	EST3X	n/a	n/a	1	10	1	2	38	32	2	n/a	n/a	n/a	UNK	UNK	n/a
Kronshage	RH	Edwards	EST3	2	40	2	22	6	27	4	30	6	n/a	1	n/a	8	2	n/a
Leopold	RH	Notifier	NFS640	4	143	6	25	11	73	594	175	10	n/a	1	n/a	UNK	UNK	90
Mack	RH	EST	EST3	1	37	1	6	9	8	42	12	4	n/a	n/a	n/a	UNK	UNK	42
Merit	RH	Simplex	4010	1	24	UNK	5	13	8	n/a	21	4	n/a	1	n/a	UNK	UNK	29
Newell Smith	RH	Simplex	4100U	6	188	17	10	1	112	240	270	14	n/a	2	n/a	UNK	UNK	436
Ogg	RH	EST	EST3	22	548	20	26	1	1	1	569	46	n/a	2	n/a	UNK	UNK	5
Phillips	RH	Simplex	4100ES	5	127	UNK	10	1	23	74	56	12	n/a	n/a	n/a	UNK	UNK	n/a
Slichter	RH	Simplex	4100	n/a	95	1	2	19	20	135	77	2	n/a	n/a	n/a	UNK	UNK	104
Sellery	RH	Siemens	MXLV	6	330	6	27	74	73	594	175	14	n/a	2	n/a	UNK	UNK	594
Showerman	RH	EST	EST3	1	30	1	10	11	7	40	9	4	n/a	n/a	n/a	UNK	UNK	40
Sullivan	RH	Simplex	4100U	4	79	1	22	19	20	135	77	10	n/a	n/a	n/a	UNK	UNK	144
Swenson	RH	EST	EST3	1	32	2	2	9	4	35	17	4	n/a	n/a	n/a	UNK	UNK	40
Tripp	RH	Simplex	4100U	4	149	UNK	27	45	47	244	69	10	n/a	n/a	n/a	UNK	UNK	240
Turner	RH	EST	EST3	1	27	1	9	8	8	39	10	4	n/a	n/a	n/a	UNK	UNK	40
Witte	RH	Edwards	EST3	46	1034	92	228	3*	87	460	224	96	17	2	1	UNK	UNK	n/a
Zoe Bayliss	RH	Notifier	5000	n/a	16	n/a	7	7	n/a	n/a	11	2	n/a	n/a	n/a	UNK	UNK	31
Harvey Street Apt Bldg 1-7	Harvey St Apts	Notifier	AFP-200	4	0	0	13	59	0	0	119	14	n/a	n/a	n/a	n/a	n/a	147

Building	Area	MFG	Panel	NAC	Smoke	Duct	Heat	Pulls	Strobe	Horn	Horn Strobe	Battery Count	Stairwell Pressure	Elevator Recall	DAS / BDA	Relay Modules	Monitor Module	110 VAC SmokeDetector
Eagle Heights Community Ctr	EH Comm Ctr	EST	IO64	0	10	3	1	10	0	0	17	2	n/a	n/a	n/a	n/a	n/a	n/a
Apartment Facilities Office	Apt Facility Office	Siemens	FS-250	1	1	0	5	3	8	0	6	2	n/a	n/a	n/a	n/a	n/a	n/a
Warehouse	WH	Siemens	FS-250	1	30	0	10	7	9	0	9	4	n/a	n/a	n/a	n/a	n/a	n/a
101	EH	Siemens	FS-250	1	7	0	2	4	4	24	4	2	n/a	n/a	n/a	n/a	n/a	24
102	EH	Siemens	FS-250	0	7	0	2	4	4	36	4	2	n/a	n/a	n/a	n/a	n/a	38
103	EH	Siemens	FS-250	0	7	0	2	4	6	36	10	2	n/a	n/a	n/a	n/a	n/a	36
104	EH	Siemens	FS-250	0	7	0	2	4	4	18	4	2	n/a	n/a	n/a	n/a	n/a	22
105	EH	Siemens	FS-250	0	7	0	2	4	4	36	4	2	n/a	n/a	n/a	n/a	n/a	36
106	EH	Siemens	FS-250	0	5	0	2	4	4	16	4	2	n/a	n/a	n/a	n/a	n/a	16
107	EH	Siemens	FS-250	0	7	0	2	4	4	24	4	2	n/a	n/a	n/a	n/a	n/a	24
108	EH	Siemens	FS-250	0	5	0	2	4	4	16	4	2	n/a	n/a	n/a	n/a	n/a	16
109	EH	Siemens	FS-250	0	7	0	2	4	4	36	4	2	n/a	n/a	n/a	n/a	n/a	36
200	EH Storage Shed	Honeywe II Firelite	ES-50x	1	0	0	12	0	7	0	0	2	n/a	n/a	n/a	n/a	n/a	0
201	EH	Siemens	FS-250	1	7	0	2	4	4	24	4	2	n/a	n/a	n/a	n/a	n/a	24
202	EH	Siemens	FS-250	0	7	0	2	4	4	36	4	2	n/a	n/a	n/a	n/a	n/a	36
203	EH	Siemens	FS-250	0	7	0	2	4	4	24	4	2	n/a	n/a	n/a	n/a	n/a	24
204	EH	Siemens	FS-250	0	7	0	2	4	4	36	4	2	n/a	n/a	n/a	n/a	n/a	36
205	EH	Siemens	FS-250	0	7	0	2	4	4	24	4	2	n/a	n/a	n/a	n/a	n/a	24
206	EH	Siemens	FS-250	0	7	0	2	4	4	36	4	2	n/a	n/a	n/a	n/a	n/a	36
207	EH	Siemens	FS-250	0	7	0	2	4	4	36	4	2	n/a	n/a	n/a	n/a	n/a	36
208	EH	Siemens	FS-250	0	3	0	2	2	24	4	22	2	n/a	n/a	n/a	n/a	n/a	28
209	EH	Siemens	FMC901-US	0	5	0	2	3	4	16	3	2	n/a	n/a	n/a	n/a	n/a	26
301	EH	Siemens	FS-250	0	11	0	2	10	4	36	7	2	n/a	n/a	n/a	n/a	n/a	36
302	EH	Siemens	FS-250	0	11	0	2	10	4	36	7	2	n/a	n/a	n/a	n/a	n/a	36
303	EH	Siemens	FS-250	2	4	0	1	2	36	2	38	2	n/a	n/a	n/a	n/a	n/a	24
304	EH	Siemens	FS-250	0	11	0	1	10	4	36	8	2	n/a	n/a	n/a	n/a	n/a	36
305	EH	Simplex	4010	0	0	0	2	9	0	0	11	2	n/a	n/a	n/a	n/a	n/a	12
306	EH	Siemens	FS-250	0	11	0	1	10	4	36	7	2	n/a	n/a	n/a	n/a	n/a	36
307	EH	Siemens	FS-250	1	11	0	1	10	8	30	13	2	n/a	n/a	n/a	n/a	n/a	36
308	EH	Siemens	FS-250	0	11	0	1	10	8	36	8	2	n/a	n/a	n/a	n/a	n/a	36
309	EH	Simplex	4007	0	0	0	2	13	0	0	32	2	n/a	n/a	n/a	n/a	n/a	17
401	EH	Siemens	FS-250	0	11	0	1	10	8	30	8	2	n/a	n/a	n/a	n/a	n/a	30
402	EH	Siemens	FS-250	1	5	0	2	2	28	4	25	2	n/a	n/a	n/a	n/a	n/a	4

Building	Area	MFG	Panel	NAC	Smoke	Duct	Heat	Pulls	Strobe	Horn	Horn Strobe	Battery Count	Stairwell Pressure	Elevator Recall	DAS / BDA	Relay Modules	Monitor Module	110 VAC SmokeDetector
403	EH	Siemens	FS-250	0	11	0	2	10	20	18	19	2	n/a	n/a	n/a	n/a	n/a	18
404	EH	Simplex	4010	0	0	0	2	13	0	0	32	2	n/a	n/a	n/a	n/a	n/a	0
405	EH	Siemens	FS-250	0	11	0	2	10	20	21	20	2	n/a	n/a	n/a	n/a	n/a	21
406	EH	Siemens	FS-250	1	4	0	2	3	8	16	14	2	n/a	n/a	n/a	n/a	n/a	16
407	EH	Simplex	4010	0	0	0	2	9	0	0	22	2	n/a	n/a	n/a	n/a	n/a	0
408	EH	Siemens	FS-250	0	11	0	3	10	16	24	16	2	n/a	n/a	n/a	n/a	n/a	24
501	EH	Siemens	FS-250	1	4	0	1	2	10	10	11	2	n/a	n/a	n/a	n/a	n/a	17
502	EH	Siemens	FS-250	0	11	0	2	10	4	36	4	2	n/a	n/a	n/a	n/a	n/a	36
503	EH	Siemens	FS-250	0	11	0	2	10	4	36	5	2	n/a	n/a	n/a	n/a	n/a	36
504	EH	Siemens	FS-250	0	11	0	2	10	16	24	17	2	n/a	n/a	n/a	n/a	n/a	36
505	EH	Simplex	4010	0	0	0	2	14	0	0	22	2	n/a	n/a	n/a	n/a	n/a	29
506	EH	Siemens	FS-250	0	11	0	2	10	4	36	4	2	n/a	n/a	n/a	n/a	n/a	36
507	EH	Simplex	4010	0	0	0	2	9	0	0	22	2	n/a	n/a	n/a	n/a	n/a	19
508	EH	Simplex	4010	0	0	0	1	9	0	0	18	2	n/a	n/a	n/a	n/a	n/a	17
509	EH	Siemens	FS-250	0	11	0	2	10	16	24	16	2	n/a	n/a	n/a	n/a	n/a	36
601	EH	Siemens	FS-250	0	8	0	2	7	4	16	3	2	n/a	n/a	n/a	n/a	n/a	16
602	EH	Siemens	FS-250	0	11	0	2	10	4	36	5	2	n/a	n/a	n/a	n/a	n/a	36
603	EH	Siemens	FS-250	0	11	0	2	10	4	24	3	2	n/a	n/a	n/a	n/a	n/a	24
604	EH	Siemens	FS-250	0	11	0	2	10	4	36	4	2	n/a	n/a	n/a	n/a	n/a	36
605	EH	Siemens	FS-250	0	11	0	2	10	4	36	5	2	n/a	n/a	n/a	n/a	n/a	36
606	EH	Siemens	FS-250	0	11	0	2	10	4	36	4	2	n/a	n/a	n/a	n/a	n/a	36
607	EH	Siemens	FS-250	0	11	0	2	10	4	24	3	2	n/a	n/a	n/a	n/a	n/a	24
608	EH	Siemens	FS-250	1	11	0	2	10	4	36	5	2	n/a	n/a	n/a	n/a	n/a	36
609	EH	Siemens	FS-250	0	8	0	2	7	4	16	3	2	n/a	n/a	n/a	n/a	n/a	16
610	EH	Siemens	FS-250	0	11	0	2	10	4	36	4	2	n/a	n/a	n/a	n/a	n/a	36
701 - 703	EH	Siemens	MXL-IQ	1	6	0	3	44	0	0	55	4	n/a	n/a	n/a	n/a	n/a	112
704 - 705	EH	Siemens	MXL-IQ	4	7	0	6	28	0	0	108	6	n/a	n/a	n/a	n/a	n/a	172
706	EH	Siemens	SXL	0	5	0	2	14	0	0	6	2	n/a	n/a	n/a	n/a	n/a	17
707	EH	Siemens	SXL	0	5	0	2	14	0	0	9	2	n/a	n/a	n/a	n/a	n/a	14
708	EH	Simplex	4010	0	6	0	2	20	0	0	32	2	n/a	n/a	n/a	n/a	n/a	37
801 - 808	EH	Siemens	MXL-IQ	3	14	0	12	56	0	0	90	8	n/a	n/a	n/a	n/a	n/a	144
809 - 819	EH	Siemens	MXL-IQ	4	21	0	16	77	0	0	99	10	n/a	n/a	n/a	n/a	n/a	198
901 - 911	EH	Siemens	MXL-IQ	4	17	0	15	77	0	0	100	10	n/a	n/a	n/a	n/a	n/a	260
912 - 914	EH	Simplex	4010	0	2	0	1	14	0	0	19	2	n/a	n/a	n/a	n/a	n/a	24
915 - 917	EH	Simplex	4010	0	2	0	1	14	0	0	19	2	n/a	n/a	n/a	n/a	n/a	24
918 - 925	EH	Siemens	MXL-IQ	0	15	0	12	54	0	0	23	8	n/a	n/a	n/a	n/a	n/a	148
926 - 928	EH	Siemens	MXL-IQ	0	3	0	3	14	0	0	18	2	n/a	n/a	n/a	n/a	n/a	36
929 - 931	EH	Siemens	MXL-IQ	0	3	0	3	14	0	0	18	2	n/a	n/a	n/a	n/a	n/a	38

Building	Area	MFG	Panel	NAC	Smoke	Duct	Heat	Pulls	Strobe	Horn	Horn Strobe	Battery Count	Stairwell Pressure	Elevator Recall	DAS / BDA	Relay Modules	Monitor Module	110 VAC SmokeDetector
932 - 934	EH	Siemens	MXL-IQ	0	3	0	3	14	0	0	18	2	n/a	n/a	n/a	n/a	n/a	36
935 - 946	EH	Siemens	MXL-IQ	4	17	0	15	81	0	0	129	10	n/a	n/a	n/a	n/a	n/a	230
1	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
2	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
3	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	22
5	UH	Siemens	FC-922	2	11	0	0	3	2	0	9	2	n/a	n/a	n/a	n/a	n/a	19
6	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	26
7	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
9	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	27
10	UH	Siemens	FC-922	2	8	0	0	1	2	0	6	2	n/a	n/a	n/a	n/a	n/a	23
11	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
13	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
14	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
15	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
17	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
18	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
19	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	22
21	UH	Siemens	FC-922	2	11	0	0	3	4	0	9	2	n/a	n/a	n/a	n/a	n/a	21
22	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
23	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
25	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
26	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
27	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	22
29	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	18
30	UH	Siemens	FC-922	2	11	0	0	3	2	0	9	2	n/a	n/a	n/a	n/a	n/a	21
31	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	27
33	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
34	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	26
35	UH	Siemens	FC-922	2	8	0	0	1	0	0	4	2	n/a	n/a	n/a	n/a	n/a	25
37	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
38	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16
39	UH Child Care Center	Edwards	IO500	2	31	0	8	11	10	0	27	2	n/a	1	n/a	n/a	n/a	n/a
41	UH	NA	NA	0	0	0	0	0	0	0	0	n/a	n/a	n/a	n/a	n/a	n/a	16

RH = RESIDENCE HALL

EH = EAGLE HEIGHTS

UH = UNIVERSITY HOUSES

WH = WAREHOUSE

UNK = UNKNOWN

*1 is Ansul